

Table 2 Removal Performance Assessment of Additional ALPS System A (Excluding ND)

Unit: Bq/cc	NC*	Before	After
Sr-90	0.03	160	0.0002
Y-90	0.3	160	0.0002
Tc-99	1	0.021	ND<0.0019
Ru-106	0.1	0.15	0.0062
Rh-106	300	0.15	0.0062
Sb-125	0.8	1	0.00069
Te-125m	0.9	1	0.00069
I-129	0.009	0.019	0.0081
Cs-134	0.06	0.26	0.00023
Cs-135	0.6	0.00001	0.0000000041
Cs-137	0.09	1.5	0.00065
Ba-137m	800	1.5	0.00065
Co-60	0.2	0.089	0.0017
Ni-63	6	0.11	ND<0.017

Note: From "Results of Analysis of Water Treated by Additional ALPS", November 2, 2016.